

City of Louisburg Public Works Department

215 S Broadway, Louisburg, Kansas 66053 (913) 837-5371 Fax (913) 837-5374

February 5, 2020

Subject: Request for Proposals for Concrete Repair

Dear Sir or Madam:

You are invited to submit a proposal for concrete sidewalk and curb repair.

The project consists of curbs and flatwork as follows:

1. Provide all labor and materials to construct the curbs and flatwork as shown on attached drawing.
2. Contractor will use AB3 if needed for base.
3. Curbs shall be stand-up type "B" and have 3 #4 rebar's.
4. Sidewalks shall have 3 #4 rebar lengthwise with crossbars. Rebar shall be on chairs. Sidewalks shall be 3 1/2" thick minimum. A 6 foot wide sidewalk shall be provided. Sidewalk elevation shall match existing storm sewer inlet.
5. All concrete shall be **KCMMB Granite 4500 psi mix**. Concrete mix shall be submitted and approved before pouring.
6. Grading will be done by Contractor
7. Two year Maintenance Bond
8. Contractor will put out door hangers no less than 2 days before the work is scheduled to start.

Work shall be completed by July 31, 2020.

Completed bids are requested by 10 am on Tuesday February 26, 2020.

If you have any questions, please feel free to call Craig Hufferd, 913-238-6324

Enclosures:

Bid Sheet

Location Drawing/Map

BID SHEET

ITEM	QTY	UNIT	UNIT PRICE	TOTAL PRICE
------	-----	------	------------	-------------

Step up curb

- | | | | | |
|----|------------------------------|--|-----------|----------|
| 1. | 201 Crestview Cir (28' x 2') | | \$ _____/ | \$ _____ |
| 2. | 1400 W Amity St (55' x 2') | | \$ _____/ | \$ _____ |

	TOTAL		\$ _____
--	-------	--	----------

Roll Back Curbs

- | | | | | |
|----|----------------------------------|--|-----------|----------|
| 3. | S 6 th St E (8' x 2') | | \$ _____/ | \$ _____ |
| 4. | 402 Aquatic Dr (10' x 2') | | \$ _____/ | \$ _____ |

	TOTAL		\$ _____
--	-------	--	----------

Sidewalk / Slab

- | | | | | |
|-----|---|--|-----------|----------|
| 5. | 1100 N 4 th Street E (8' x 4') | | \$ _____/ | \$ _____ |
| 6. | 1102 N 1 st Street E (8' x 4') | | \$ _____/ | \$ _____ |
| 7. | N Rockville Rd (20'x5')(13'x5')(17'x5')(12'x5') | | \$ _____/ | \$ _____ |
| 8. | 1023 S 11 th St (8' x 4') | | \$ _____/ | \$ _____ |
| 9. | 1132 S 12 th St (8' x 4') | | \$ _____/ | \$ _____ |
| 10. | 1400 W Amity St (12' x 5') | | \$ _____/ | \$ _____ |
| 11. | 100 W Crestview Dr (10' x 4') | | \$ _____/ | \$ _____ |
| 12. | 100 W Crestview Dr (11' x 5') | | \$ _____/ | \$ _____ |
| 13. | 402 Aquatic Dr (40' x 6') | | \$ _____/ | \$ _____ |

	TOTAL		\$ _____
--	-------	--	----------

Pending if needed bid:

- | | | | | |
|-----|---|--|-----------|----------|
| 14. | Sidewalk – 600 Broadmoor Cove (58' x 4') | | \$ _____/ | \$ _____ |
| 15. | Rollback curb – 600 Broadmoor Cove (58' x 2') | | \$ _____/ | \$ _____ |

	TOTAL		\$ _____
--	-------	--	----------

Company _____

Address _____

Phone _____

Signature _____

Concrete Work (will be marked with white paint):







